

Inverter Stud Welder



PROCESS	:	DRAWN-ARC
WELDABLE STUD RANGE	:	M 8-M 25
MAX CURRENT	:	2500 AMPS
WELD TIME	:	10-3000 msec
MAINS POWER 50/60HZ 3 PHASE	:	400 VOLTS
MAIN PLUG AT 400 V	:	170 AMPS.
GUN	:	DAP-25
KVA	:	115 KVA
HOUSING DIMENSIONS (LXWXH)	:	650 X 400 X 800
WEIGHT	:	110 KG.
Technical Details Subject To Changes Without Notice.		